

Testing — ICECREAM 4.9 UP (6.7 m)

ICECREAM 4.9 UP | 29 September 2026

Client: — no client selected —

DIMENSIONS & BODY OPTIONS

Length (m)	6.7	Width (m)	2.6	Height (m)	2.6
DOOR TYPE	DRD — PU (0.120 m)		FRONT		PU (0.120 m)
SIDES	PU (0.120 m)		ROOF		PU (0.125 m)
FLOOR INSULATION	PU (0.100 m)		INSULATION FOAM		32D PU FOAM

Category	Subtotal (R)
FRONT	3,174.13
DRD	6,938.39
DRD DOOR FITTINGS	6,340.75
SIDES	18,169.67
ROOF	9,432.17
FLOOR	21,204.60
ALUMINIUM	10,994.40
SUB FRAME + LIGHT BOX ASSY	10,508.11
REAR FRAME & FLOOR PLATE	5,799.93
SPRAY PAINTING	750.00
REFLEXITE TAPE	290.70

Materials Cost	R 93,602.85
TOTAL COST	R 93,602.85

Category	Material	SAP Code	Formula	Quantity	Unit	Unit Price (R)	Waste %	Line Cost (R)
FRONT								
	Rhinotex 1150 BW		$(\text{width} - \{\text{SIDES EPS}\} - \{\text{SIDES PU}\} - \{\text{SIDES EPS}\} - \{\text{SIDES PU}\} + \{\text{Waste}\}) * (\text{height} - \{\text{ROOF EPS}\} - \{\text{ROOF PU}\} - \{\text{FLOOR EPS}\} + \{\text{Waste}\})$	6.09	m²	213.11		1,296.83
	GLUE LINE		$(\text{width} - \{\text{SIDES EPS}\} - \{\text{SIDES PU}\} - \{\text{SIDES EPS}\} - \{\text{SIDES PU}\} + \{\text{Waste}\}) * (\text{height} - \{\text{ROOF EPS}\} - \{\text{ROOF PU}\} - \{\text{FLOOR EPS}\} + \{\text{Waste}\})$	6.09	m²	28.58		173.92
	GLUE LINE		$(\text{width} - \{\text{SIDES EPS}\} - \{\text{SIDES PU}\} - \{\text{SIDES EPS}\} - \{\text{SIDES PU}\} + \{\text{Waste}\}) * (\text{height} - \{\text{ROOF EPS}\} - \{\text{ROOF PU}\} - \{\text{FLOOR EPS}\} + \{\text{Waste}\})$	6.09	m²	28.58		173.92
	4MM PF PLYWOOD		$(\text{width} - \{\text{SIDES EPS}\} - \{\text{SIDES PU}\} - \{\text{SIDES EPS}\} - \{\text{SIDES PU}\} + \{\text{Waste}\}) * (\text{height} - \{\text{ROOF EPS}\} - \{\text{ROOF PU}\} - \{\text{FLOOR EPS}\} + \{\text{Waste}\}) * 0$	0.00	m²	68.79		0.00
	GLUE LINE		$(\text{width} - \{\text{SIDES EPS}\} - \{\text{SIDES PU}\} - \{\text{SIDES EPS}\} - \{\text{SIDES PU}\} + \{\text{Waste}\}) * (\text{height} - \{\text{ROOF EPS}\} - \{\text{ROOF PU}\} - \{\text{FLOOR EPS}\} + \{\text{Waste}\})$	6.09	m²	28.58		173.92
	Rhinotex 1150 Bioshield		$(\text{width} - \{\text{SIDES EPS}\} - \{\text{SIDES PU}\} - \{\text{SIDES EPS}\} - \{\text{SIDES PU}\} + \{\text{Waste}\}) * (\text{height} - \{\text{ROOF EPS}\} - \{\text{ROOF PU}\} - \{\text{FLOOR EPS}\} + \{\text{Waste}\})$	6.09	m²	222.76		1,355.55
FLOOR								
	Rhinotex 1150 BW		$(\text{length} + \{\text{Waste}\}) * (\text{width} + \{\text{Waste}\})$	17.89	m²	213.11		3,812.01
	GLUE LINE		$(\text{length} + \{\text{Waste}\}) * (\text{width} + \{\text{Waste}\})$	17.89	metre	28.58		511.28
	GLUE LINE		$((\text{length} + \{\text{Waste}\}) * (\text{width} + \{\text{Waste}\})) * 3$	53.66	metre	28.58		1,533.85
	18 MM PF PLYWOOD		$((\text{length} + \{\text{Waste}\}) * (\text{width} + \{\text{Waste}\})) / 2.98$	6.00	m²	798.00		4,790.01
	76*50*2 R.T. TUBE		$(6.7 + \{\text{Waste}\}) / 1.05 * 3$	19.29	each	102.23		1,971.58
	228*50 TIMBER		$(\text{width} + \{\text{Waste}\}) * 2$	5.30	each	146.59		776.95
	100*50 LVL Beam		$((6.7 + \{\text{Waste}\}) / 0.416 - 6.75 / 1.05) * 3$	29.39	metre	146.59		4,308.74

Category	Material	SAP Code	Formula	Quantity	Unit	Unit Price (R)	Waste %	Line Cost (R)
	2*300 INT LAMINATION		$((6.7 + \{Waste\}) + 0.4) * ((width + \{Waste\}) + 0.7) * 2$	47.91	m²	50.15		2,402.63
	ANTI-SKID FINAL COAT		$((6.7 + \{Waste\}) + 0.4) * ((width + \{Waste\}) + 0.7) * 2 / 2$	23.95	m²	45.82		1,097.55
DRD								
	Rhinotex 1150 BW		$(width - \{SRD\ EPS\} - \{SRD\ PU\} - \{SIDES\ EPS\} - \{SIDES\ PU\} + \{Waste\}) * (height - \{ROOF\ EPS\} - \{ROOF\ PU\} - \{FLOOR\ EPS\} + \{Waste\})$	6.39	m²	213.11		1,361.40
	GLUE LINE		$(width - 0.12 + \{Waste\}) * (height - 0.125 + \{Waste\})$	6.39	m²	28.59		182.64
	PU		$(1.22 * 2.44 * \{DRD\ PU\} / 2.98) * (1.22 * 2.44) * 2$	0.71	m²	4,100.00		2,926.03
	GLUE LINE		$(width - 0.12 + \{Waste\}) * (height - 0.125 + \{Waste\})$	6.39	m²	28.59		182.64
	4MM PF PLYWOOD		$(width - 0.12 + \{Waste\}) * (height - 0.125 + \{Waste\}) * 0$	0.00	m²	68.79		0.00
	GLUE LINE		$(width - 0.12 + \{Waste\}) * (height - 0.125 + \{Waste\})$	6.39	m²	28.59		182.64
	Rhinotex 1150 Bioshield		$(width - 0.12 + \{Waste\}) * (height - 0.125 + \{Waste\})$	6.39	m²	222.76		1,423.05
	130*62MM TAPPING BLOCKS_200MM		5	5.00	each	68.00		340.00
	130*62MM TAPPING BLOCKS_250MM		5	5.00	each	68.00		340.00
DRD DOOR FITTINGS								
	CSLB HINGES		6	6.00	each	146.73		880.38
	SB 51111 DOOR SET		2	2.00	each	506.91		1,013.82
	LOCKING POLE		$(height - 0.125 + \{Waste\}) * 2$	5.05	each	42.00		212.10
	28779 DOOR CAPPING		$((height - 0.125 + \{Waste\}) * 3 + (width - 0.12 + \{Waste\}) * 2)$	12.63	metre	149.08		1,883.63
	28777 DOOR CAPPING		$(height - 0.125 + \{Waste\})$	2.52	metre	132.13		333.63
	2316 DOOR RUBBER		$((height - 0.125 + \{Waste\}) * 3 + (width - 0.12 + \{Waste\}) * 2)$	12.63	metre	24.72		312.34
	2317 DOOR RUBBER		$((height - 0.125 + \{Waste\}) * 3 + (width - 0.12 + \{Waste\}) * 2)$	12.63	metre	60.18		760.37
	M10*40 GALV. BOLTS		40	40.00	each	0.50		20.00

Category	Material	SAP Code	Formula	Quantity	Unit	Unit Price (R)	Waste %	Line Cost (R)
	M10 SPRING WASHERS		38	38.00	each	0.13		5.10
	0661-0631 LONG RIVETS		100	100.00	each	0.52		51.50
	SILPLUS X WHITE SILICONE		2	2.00	each	116.15		232.30
	3MM ALU BUFFER PLATE		2	2.00	each	164.57		329.15
	T-BAR CATCH		2	2.00	each	56.00		112.00
	D-RUBBER		2	2.00	each	97.22		194.44
SIDES								
	Rhinotex 1150 BW		$(6.7 + \{Waste\}) * (height - 0.125 + \{Waste\})$	34.09	m²	213.11		7,264.39
	GLUE LINE		$(6.7 + \{Waste\}) * (height - 0.125 + \{Waste\})$	34.09	m²	28.59		974.56
	GLUE LINE		$(6.7 + \{Waste\}) * (height - 0.125 + \{Waste\})$	34.09	m²	28.59		974.56
	4MM PF PLYWOOD		$(6.7 + \{Waste\}) * (height - 0.125 + \{Waste\}) * 0$	0.00	m²	68.79		0.00
	GLUE LINE		$(6.7 + \{Waste\}) * (height - 0.125 + \{Waste\})$	34.09	m²	28.59		974.56
	Rhinotex 1150 Bioshield		$(6.7 + \{Waste\}) * (height - 0.125 + \{Waste\})$	34.09	m²	222.76		7,593.33
	3MM MILD STEEL PLATE		$(height - 0.125 + \{Waste\}) * 2 * 0.1$	1.01	each	384.42		388.26
ROOF								
	Rhinotex 1150 BW		$(6.7 + \{Waste\}) * (width + \{Waste\})$	17.89	m²	213.11		3,812.01
	GLUE LINE		$(6.7 + \{Waste\}) * (width + \{Waste\})$	17.89	m²	28.58		511.22
	GLUE LINE		$(6.7 + \{Waste\}) * (width + \{Waste\}) * 2$	35.77	m²	28.58		1,022.45
	Rhinotex 1150 Bioshield		$(6.7 + \{Waste\}) * (width + \{Waste\})$	17.89	m²	222.76		3,984.62
	3MM MILD STEEL PLATE		$(width + \{Waste\}) * 0.1$	0.27	each	384.42		101.87
ALUMINIUM								
	28782 BIG HORIZONTALE CAP		$((6.7 + \{Waste\}) * 4 + height + height)$	32.20	each	240.58		7,746.68
	28780 SMALL VERTICAL		$(width + \{Waste\}) * 2$	5.30	each	203.25		1,077.22
	0661-0631 LONG RIVETS		$((6.7 + \{Waste\}) * 4 + height + height) * 20 + (width + \{Waste\}) * 2 * 20 + 16)$	766.00	each	0.52		394.49
	SILPLUS - X WHITE		$6.7 * 2$	13.40	each	116.15		1,556.41
	BIG ALU CORNERS		4	4.00	each	54.90		219.60
SUB FRAME + LIGHT BOX ASSY								

Category	Material	SAP Code	Formula	Quantity	Unit	Unit Price (R)	Waste %	Line Cost (R)
	5MM 300 WA PLATE		$(6.7 + \{\text{Waste}\}) * 2$	13.50	each	243.00		3,280.50
	100*50*3MM CROSS MEMBER		$0.85 * 6$	5.10	each	243.00		1,239.30
	SPRING MOUNTING		2	2.00	each	162.90		325.80
	BIG MOUNTING BRACKETS		4	4.00	each	380.64		1,522.55
	SMALL MOUNTING BRACKET		4	4.00	each	68.80		275.18
	TOP CLEAT		4	4.00	each	33.50		134.00
	BOTTOM CLEAT		4	4.00	each	68.80		275.18
	BIG FISH PLATE		2	2.00	each	78.94		157.89
	3MM LIGHT BOX		$0.33 * 2.44$	0.81	m²	384.42		309.53
	100*50TAPER CHANNEL		4.4	4.40	each	124.68		548.59
	100*50RSC BUMPER		3	3.00	each	167.92		503.76
	2MM CHEVRON PLATE		$0.22 * 2.44$	0.54	m²	267.87		143.79
	1.7 MTR CHEVRON BOARD		1	1.00	each	165.00		165.00
	115MM RED TRUCK LIGHTS		2	2.00	each	115.00		230.00
	115MM AMBER TRUCK LIGHTS		2	2.00	each	115.00		230.00
	CROME NO.PLATE LIGHTS		1	1.00	each	50.00		50.00
	3MM MUD FLAP PLATES		$0.61 * 0.61$	0.37	m²	384.42		143.04
	M10*30 GALV BOLTS		6	6.00	each	0.50		3.00
	M10 NYLOCK NUT		6	6.00	each	0.74		4.42
	ICB MUDFLAP		1	1.00	each	384.42		384.42
	1.2MM GALV PLATE		$0.61 * 1.225 * 2$	1.49	each	300.78		449.52
	SILPLUS X-WHITE		1	1.00	each	116.15		116.15
	0661-0631 RIVETS		32	32.00	each	0.52		16.48
REAR FRAME & FLOOR PLATE								
	3MM 3CR12 REAR FRAME		$0.27 * \text{height} * 2$	1.40	each	965.76		1,355.93
	TOP FRAME RAIN GUTTER		$0.305 * \text{width}$	0.79	metre	965.76		765.85
	3MM 3CR12 FLOOR PLATE		$1.25 * 2.5$	3.12	m²	965.76		3,018.02

Category	Material	SAP Code	Formula	Quantity	Unit	Unit Price (R)	Waste %	Line Cost (R)
	SILPLUS X-WHITE		3	3.00	each	116.15		348.45
	M8*150 GALV. CUP SQUARES		15	15.00	each	2.50		37.50
	M8*45*3 FENDER WASHER		15	15.00	each	0.21		3.19
	M8 NYLOCK NUT		15	15.00	each	0.34		5.03
	5MM CORNER GUSSET		2	2.00	each	89.20		178.40
	2771-0824 MONOBOLTS		24	24.00	each	3.65		87.58
SPRAY PAINTING								
	PAINTING OF SUB FRAME + REAR FRAME		1	1.00	each	750.00		750.00
REFLEXITE TAPE								
	50MM REFLEXITE TAPE		$((\text{width} + \{\text{Waste}\}) + (6.7 + \{\text{Waste}\}) * 2)$	16.15	metre	18.00		290.70